



# PURE ELECTRIC

THE POWER TO BE FREE

Beyond the Grid Pty Ltd trading as Pure Electric Solutions

ABN: 67 603 174 661 | ACN: 603 174 661

Phone: 1300 TO PURE (1300 86 7873) | Email: info@pure-electric.com.au

## TAX INVOICE #2004

Billing Address		Install Address	Prepared By	
Langdon Building Pty Ltd Lot 219 Kensington Boulevard SMYTHES CREEK VIC 3351		Langdon Building Pty Ltd 9 Kensington Boulevard SMYTHES CREEK VIC 3351	Lu Pham	
Invoice Date		Due Date		
25/06/2020		01/07/2020		
Invoice Number		Paid	Due	
2004		\$4,690.00	\$0.00	
Qty	Product	Description	Sale Price	Total
1	Sanden Eco Plus 315L Complete Heat Pump System GAUS-315FQS	Highest efficiency heat pump hot water system in Australia - COP 5.6 82% energy savings vs electric, 88% vs conventional gas 315L Stainless Steel Tank 1748mm x 621mm, 10 + 5 pro rata warranty, Australia Made (GAUS-315FQS) Heat pump 895mm x 754mm x 362mm, 6 year warranty, Japan made 15mm AVG Quick Connection Kit and custom fit lagging (QIK15-HPUMP) Includes Sanden Heat Pump Feet (x4) Delivery included when installed by our team GAUS-315FQS Delivery included when installed by our team Install 315L Sanden Eco Plus complete heat pump stainless steel storage tank on owner/builder provided concrete pad. Install the heat pump on ground next to tank on owner/builder concrete pad. Install a 500kpa pressure limiting valve. Install tempering valve to protect the unit. Install NRI PRV valve (acts as Duo valve) on cold water feed to tank. Install using AVG 15mm Plumbing Quick Connection, all inclusive. Connect the tank in 15mm copper to the owner/builder provided hot and cold feeds next to tank. Lag all hot pipes with solar rated insulation. Install PTR with insulated glove. Run drain line in 15mm copper to discharge point provided by owner/builder and no more than two meters from tank. Note: Owner/builder responsibility to ensure that discharge point is in accordance with regulations. Run clear drain hose from drain connector on heat pump to discharge point provided by owner/builder and no more than two meters from heat pump. Owner/builder electrician wire up unit with isolator and 20A circuit fitted with a circuit breaker. Issue Plumbing Certificate of Compliance for the work completed.	\$5,345.45	\$5,345.45
34	STC Rebate	Small-scale technology certificates (STC) - Rebate provided as a point of sale discount (GST not applicable)	\$-35.00	\$-1,190.00
1	Sanden Standard Plumbing Install	Premium lagging Commissioning Certificate of Compliance		

Sub Total \$4,155.45

GST 10% \$534.55

**Grand Total \$4,690.00**

Installation Date: 01/07/2020

Equipment and Model: GAUS-315FQS

Tank Serial: 9580000003485

HP Serial: 2020.04-6003603

Plumbing PIC: 15289543

## Payments Received:

26 Jun 2020 BSB Transfer REF: From:LANDGON BUIL REF: Invoice 2004 ePayment \$4690 Deposit