

PURE ELECTRIC

Beyond the Grid Pty Ltd trading as Pure Electric Solutions ABN: 67 603 174 661 ACN: 603 174 661 | 38 Ewing St, Brunswick VIC 3056 Phone: 03 8658 0733 | Email: info@pure-electric.com.au

TAX INVOICE #2428

| TAX INVOICE #2428 | | | | | | | | | | |
|-----------------------|---|-------------------------|--------------------------------------|---|---------------|-------------|------------|--|--|--|
| Billing Address | | | Install Address | | | Prepared By | | | | |
| 31 M Carn VIC 3 | 3163 | | 31 Morgan St Carnegie VIC 3163 | | | Amy Ho | | | | |
| | ice Date | | Due Date | | | | | | | |
| | 1/2020 | | 10/11/2020 | | | | | | | |
| Invoice Number | | | | Paid Due | | | | | | |
| 2428 | | | | \$5,350.00 | | | | | | |
| Qty | Product | Part Num | ber | Description | Pri | _ | Total | | | |
| 1 | Sanden Eco Plus Heat Pump Supply and Installation | SSI | | Sanden Eco Plus Heat Pump Supply and Installation Supply of the complete Sanden heat pump hot water system Installation using our experienced team | \$5,465.45 \$ | | \$5,465.45 | | | |
| 1 | Sanden Eco Plus 250L Complete Heat Pump System GAUS- 250FQS | GAUS-250FQS | | Highest efficiency heat pump hot water system in Australia - COP 5.96 82% energy savings vs electric, 88% vs conventional gas 250L Stainless Steel Tank 1428mm (h) x 621mm (d), 15 years pro-rata warranty, Australia Made (SAN-250SAQA) Heat pump 895mm x 754mm x 362mm, 6 year warranty, Japan made (GAU-A45HPC) 4x Feet for Sanden Heat Pump Feet (HPFT-1) GAUS-250FQS | | | | | | |
| 1 | Sanden Plumbing Quick Connection Kit 15mm | QIK15-HPUMP | | Quick Connection Kit 15mm Dedicated Sanden AVG installation components with custom fit lagging NRI-PRV-15C Combo Valve with lagging ECV Cold Water Expansion Valve Custom fit lagging - elbows, valves (not available separately) to comply with AS3500 PTR Insulation Glove | | | | | | |
| 1 | Sanden Standard Electrical Install | Sanden_Elec_Install_Std | | Connection by qualified electrician to prepared power Certificate of Electrical Safety (CES) | | | | | | |
| 1 | Sanden Standard Plumbing Install | Sanden_Plb_Install_Std | | Premium lagging Commissioning Certificate of Compliance Assumes customer cold water inlet pressure is maximum 500kPa in accordance with AS3500 Will be installed in accordance with AS3500 to Australian Standards up to 500kPa Free removal of old accessible ground external hot water system (if required) | | | | | | |

Page 1 17/11/2020

| 1 | Sanden Pavers 2x 450x450 | Sanden_HP_Pavers | 2x 450mm x 450mm pavers for Heat Pump (required if area not paved / stable), plumber to supply and install | | |
|----|-----------------------------|------------------------|---|----------|-------------|
| 1 | Sanden Tank 600x600 Slab | Sanden_Tank_Slab | 600mm x 600mm slab for Sanden tank, plumber to supply and install | | |
| 34 | STCs | STC Rebate Certificate | Small-scale Technology Certificates (STCs) - Financial Incentive provided as a point of sale discount (GST included only when sold to a GST registered entity) | \$-33.00 | \$-1,122.00 |
| 1 | Sanden Electrical Extra | SANDEN_ELEC_EXTRA | Dedicated circuit 20A | \$200.00 | \$200.00 |
| 1 | Pressure Reduction Valve | PRV | Supply and Install Pressure Reduction Valve (PRV) to drop mains water pressure down to max 500kPa Ensures compliance with AS3500 so that, "The maximum static pressure at any outlet, other than a fire service outlet, within a building must not exceed 500 kPa." | \$218.18 | \$218.18 |

Sub Total \$4,761.63

GST 10% \$588.37

Grand Total \$5,350.00

HOW TO PAY
Direct Deposit
Account Name: Beyond The Grid Pty
Ltd
BSB: 814-282

Account No.: 50514152

Installation Date: 06/11/2020 00:00 Equipment and Model: Sanden GAUS-250FQS

Tank Serial: 9570000001530 HP Serial: 2020.08-6004407

Plumbing PIC: 15461537

Page 2 17/11/2020